

CLIENT

Newmont Australia

LOCATION

Mt Leyshon Mine, Charters Towers

CONTRACT VALUE

\$940,000

PROJECT DURATION

August 2017 – November 2017

PROJECT REFEREE

Glen Ware – Senior Closure Planner 0417 177 283

Dave Young – Closure Superintendent 0417 639 380

PROJECT TEAM

Project Manager: Peter Bell

Site Supervisor: Shaun Sheahan



PROJECT SYNOPSIS

- 2,000m of full width insitu stabilisation pavement repairs
- 3,000m of minor pavement repairs
- 20, 000m² of bitumen seal
- Reconstruction of floodway
- Rehabilitation of severely scoured batters on Roche Hill
- 14,800m³ of embankment fill
- 7,000m³ of topsoiling
- 3,400m³ of rock fill.

Project Overview

Milray Contracting were awarded the \$940,000 package from Newmont Australia as part of the company's ongoing commitment to the rehabilitation of their Mt Leyshon mine site. The contract was awarded based on value for money and a proven track record of delivery of projects of a similar nature for Newmont Australia and other local mining companies.

The package involved the rehabilitation of the mine access road which had deteriorated over time and 2 locations on site where a waste dump and a tailings dam had been scoured by rain during an earlier cyclone event. The access road was rehabilitated using a combination of full width insitu stabilisation and smaller pavement repairs followed by bitumen sealing. The on-site rehabilitation involved repairing of scours on steep waste rock dumps and tailings dams and involved filling of scours with rock fill, placement of embankment fill, topsoiling and the construction of water diversion and silt control structures. The construction is being completed primarily using Milray Contracting plant plus some dry hire of articulated haul trucks. The project is currently ongoing.